
## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	60	UNTY	TOTAL SHEETS	SHEET NO.
SBJ 119		CHAMPAIGN		26	18
FED. ROAD CIST, NO. 7		BLUMDIS	FED. AID PROJECT-		

SHEET NO. 3

3 SHEETS

Contract Number: 70669




## PARTIAL CROSS SECTION

(Looking East)

\*\*\* Limits of HMA Surface Removal. Existing waterproofing to remain.

Lap new waterproofing 6" over existing.



## TYPICAL SECTION AT ABUTMENTS

\* Existing dowel rods are to be burned off, ground flush, and sealed with epoxy prior to placement of new beams. Cost included in Removal of Existing PPC Deck Beams. After beams have been erected holes shall be drilled into cap and dowel rods placed. Dowel holes shall be filled with non-shrink grout to top of beam and allowed to cure a minimum of 24 hours prior to grouting the shear keys.

\*\* 1" Joint shall be filled with non-shrink grout. Dimension

may vary to accommodate tolerance in beam lengths.

DESIGNED		VHV		
CHECKED		SJB		
DRAWN	Ь	baliva		
CHECKED	VHV	SJB		

REPAIR DETAILS SBI 119 CHAMPAIGN COUNTY SN 010-0062